

FG Wilson Sound Proof Generator Used Like New

FG Wilson , Sound Proof Generator Since New

Good generator , Full load Testing

Running Hours  900 HR



| SOUND PROOF FG WILSON Data & INFO |                          |
|-----------------------------------|--------------------------|
| MANUFACTURER                      | Caterpillar (NI) Limited |
| MODEL                             | P715-3                   |
| MONTH/YEAR OF MANUFACTURE         | 12/2016                  |
| RATED POWER                       |                          |
| STANDBY                           | 713.80 KVA               |
|                                   | 571 KW                   |
| PRIME                             | 625 KVA                  |
|                                   | 500 KW                   |
| AMBIENT TEMP.                     | 25 °C                    |
| RATED VOLTAGE                     | 415/240 V                |
| PHASE                             | 3                        |
| RATED POWER FACTOR                | 0.80 cos                 |
| RATED FREQUENCY                   | 50 Hz                    |
| RATED CURRENT STANDBY             | 993 A                    |
| RATED CURRENT PRIME               | 870 A                    |
| RATED RPM                         | 1500 rpm                 |
| ALTITUDE                          | 100.0 m                  |
| ALTERNATOR CONNECTION             | S STAR                   |
| 180 8528-3 RATING                 | PR 500H TL8.875          |
| ALTERNATOR ENCLOSURE              | 23 IP                    |
| INSULATION CLASS                  | H                        |
| EXCITATION VOLTAGE                | 53 V                     |
| EXCITATION CURRENT                | 4 A                      |

