

FG Wilson Sound Proof Generator Used Like New

FG Wilson , Sound Proof Generator Since New

Good generator , Full load Testing

Running Hours  900 HR



SOUND PROOF FG WILSON Data & INFO	
MANUFACTURER	Caterpillar (NI) Limited
MODEL	P715-3
MONTH/YEAR OF MANUFACTURE	12/2016
RATED POWER	
STANDBY	713.80 KVA
	571 KW
PRIME	625 KVA
	500 KW
AMBIENT TEMP.	25 °C
RATED VOLTAGE	415/240 V
PHASE	3
RATED POWER FACTOR	0.80 cos
RATED FREQUENCY	50 Hz
RATED CURRENT STANDBY	993 A
RATED CURRENT PRIME	870 A
RATED RPM	1500 rpm
ALTITUDE	100.0 m
ALTERNATOR CONNECTION	S STAR
180 8528-3 RATING	PR 500H TL8.875
ALTERNATOR ENCLOSURE	23 IP
INSULATION CLASS	H
EXCITATION VOLTAGE	53 V
EXCITATION CURRENT	4 A

